


Extract from Campus-Masterplan 09/ 2016


Ralph J. Steinhagen for the FC²WG & FCC-WG, based on previous work and input from:
Ch. Arzinger-Mayer, K. Berkl, J. Lindenberg, A. Fischer, P. Spiller, R. Bär, C. Omet, D. Ondreka,
S. Reimann (deputy), U. Scheeler, P. Schütt, G. Stephan (CE), M. Schwickert


special thanks: R. Giachino, M. Lamont, D. Manglunki, R. Steerenberg (CERN)

- Discontinued 17.1 MCR option: issues w.r.t. accessibility, being a controlled area, ... (ECR in 2015)
- New control room and additional support infrastructure needed for FAIR
 - Existing GSI “alt-HKR” is
 - A) too small for an effective commissioning & operation, and
 - need long-term ~25 ‘workstations’ (8+ accelerators, ↔ > 600 m²)
 - B) not adapted to new FAIR control & OP paradigms
 - analog signals (manual labour-intensive operation), unsafe/unsustainable w.r.t. machine protection and high-intensity operation
 - Single common platform for more efficient accelerator operation, communication across different domains, ... → improved facility performance (i.e. no multitude of local control rooms)
 - Positive public portrayal of GSI & FAIR: core facility/experiments in-accessible to public and most scientific visitors → FCC being the ‘heart’ & ‘brain’ of the facility
- [Abstracted previous site-specific concepts](#) → [generic FCC user-requirements](#)
→ [became input to Campus Master Plan \(CMP\)](#)
 - mainly site/building parameters/recommendations: location, outer hull and additional infrastructure, also “HKR”
→ “FAIR Control Centre (FCC)”
- FAIR Management reviewed CMP in 2016: confirmed FCC prioritisation within CMP, decided for ‘new building’ option, and to continue detailed & expedient planning targeting a soon-as-reasonable-achievable realisation

- **Today: presentation of accelerator operation related FCC user-requirements (80% of the input to CMP)**
 - update involved present and future stake-holders on current state
 - link to ‘FAIR Accelerator Control and Operation’ concept (dealt by FC²WG)
 - basis for further in-depth detailing of user-requirements in view of tendering process
- **Next Steps via FCC Project-Group** (smaller circle, interest-based representation/mandate)
 - **Elaborate missing requirements from other groups tightly intertwined with accelerator: Cryo, TI, (accelerator-kin) experiments, ... → remaining 20% of input to CMP**
- **Two new aspects since 2016:**
 - **office spaces above main control room: collection of user-requirements, development of usage concept, ...**
 - **main control room planning combined/advanced with primary building tranche → FCC user-requirements need to be finalised by March ‘17 to minimise overall planning costs and potential additional post-award contract charges afterwards**








- ➔ 8% LEBT / MEBT / HEBT
- ➔ Arbeitsplätze Quellen unzusammenhängend
- ➔ Konsolen sehr tief für Oszi + Röhren (teilw. obsolet)
- ➔ "Analog Betrieb"...

Farbcodes:
 Quelle
 Beschleuniger
 Speicherring
 Experiment

courtesy C. Omet





328 m² Grundfläche
200 m² Nutzfläche

60% eff. Nutzfläche

- ➔ 41% für Konsolen, Bedienflächen
- ➔ 39% für Wege
- ➔ 14% „tote“ Flächen für Wartung
- ➔ 6% für Sitzecke, etc.


courtesy C. Omet






- similar number of accelerators to FAIR, but
- lower complexity (shorter chains)
- quasi-static operation (infrequent ion-type changes per year)

$$\mathcal{O}(n^4)$$



- similar complexity/number of accelerators, but
- quasi-static operation & primarily (anti-)protons only


$$O(n^5)$$




- similar complexity/number of accelerators, but
- semi-static operation (mode of operation change typically ~ weeks → months)

$$O(n^5)$$

- A) Much larger facility, cannot reliably extrapolate from present 'UNILAC→SIS18→ESR' operation to requirements for FAIR (3 → 9+ accelerator(-like) structures)
- B) Will be in a constant flux of frequent adaptations to new cycles/beam parameters, etc. present estimate:
- 1) avg. experiment run: ~ 1-2 weeks per exp. + many new storage rings and transfer lines with high(er) complexity → machine setup time-scale
 - increased number of users & parallel operation
 - added complexity: long accelerator daisy chains $O(n^5)$
 - present efficiency for physics $\epsilon_{\text{UNILAC+SIS18}} \sim$ up to 75% → >90% (target, see appendix)
 - 2) high-intensity operation requires more and better fine-tuning
 - dynamic vacuum, machine protection & activation, collective effects
 - 3) limited operator resources: 4-5 (beam operation) + 1 (infrastructure, cryo)
- need to be smart and develop efficient commissioning procedures, training and tools to facilitate fast turn-around and to maintain/improve present operational performance
- control and operation aspects are reflected in FCC design/user-requirements





see Appendix for detailed functional user-requirements that went into the CMP



'No pillars user-requirement':

- impedes line-of sight
 - less efficient eye-to-eye com.
 - visibility of shared fixed-displays
 - Non-ideal visitor's view
- limits console layout/future upgrade options

“room' must not get in the way of the primary purpose of the room”

The 5m ceiling height avoids the “parking house effect” and is also beneficial for the acoustics, ventilation system, indirect lighting and fixed-display concept




Courtesy D. Manglu

- Existing GSI Facility Operation:
 - 3 operators for 3 accelerators and ~ 300 m² control room surface area
- Possible FAIR Operation – naïve scaling
(minimal automatisisation/tuning, truly independent parallel operation, etc.)
 - A) MSV 0-3: 7 operators for 8 accelerators and 700 m²
 - B) MSV 0-6: 12 operators for 12 accelerators and 1200 m²
- Gretchen Frage: "How many operators will be effectively needed?"
 - Important boundary conditions:
 - 1 operator doing 24h/7 shift-operation = 7.4 "real/gross" operators (FTEs) = ~ >0.5 MEUR/year → '4+1' vs. '7-8' corresponds to ~2 MEUR/Jahr (+ new offices)
 - 7-8 operators probably mainly needed during peak hours (day) (recommissioning, setting-up of new experiments/beams, etc.)
 - 'full utilisation during rush hours' vs. 'skeleton crew operation'


- *Beam-Production-Chain:*

- organisational structure to manage parallel operation and beam transfer through FAIR accelerator facility
- defines sequence and parameters of beam line from the ion-source up to an experimental cave (e.g. APPA, CBM, SuperFRS, ...)
- definition of target beam parameters (set values): isotope, energy, charge, peak intensity, slow/fast extraction, ...




- *Beam Pattern:*

- grouping of beam production-chains that are executed periodically
- can be changed of pattern within few minutes (target, requires automation for beam-based retuning)



- 'One Operator per Accelerator Domain' vs. 'One Operator per Experiment':



- Option 1: One Operator per Accelerator Domain:
 - Highly-specialised operators (less accelerator physicists needed)
 - High risk of blocking of single operators/‘congestion’ (notably for UNILAC, SIS18 & SIS100)
 - Poor OP utilisation in case only one of 4+ experiments is in operation
 - Less redundancy → permanently more operators are needed
 - 58 vs. 32 Operators (for comparison CERN OP: 90 total)
 - N.B. on OP shift = 7-8 operators ↔ ~ 0.5 MEUR/year
- Option 2: One Operator per BPC/Experiment
 - More efficient machine-machine / machine-experiment interfaces
 - Less overhead, more efficient handover of beam and adjustments to exp. Requirements
 - Motivational factor of ‘operator BPC ownership’ (i.e. “my experiment“)
 - Possibility of reduced operation crew (e.g. 32-35 for full FAIR acc. OP)
 - Broader Operator training required (not only machine-specifics)
 - ... supported by accelerator experts for setting up of new cycles, experiments and peak-times (e.g. recommissioning after technical stops, etc.)
 - Mandatory semi-automation of frequent accelerator processes (also needed for safe high-intensity operation)
 - Better redundancy within OP crew in case of illness, parental leave, holidays, etc.
 - Better value for overall organisational costs (Skeleton Crew + ‘Acc. Support Team’ when needed)

Proposed FAIR Operation – improved scaling

A) 'Skeleton Crew': 4+2+1 people (monitoring, notably during night shift)


- 4-5 parallel experiments x 1 operator/experiment
- 1-2 Cryo-Operators (SIS100, SuperFRS)
- 1 TI Operator (acc. related infrastructure: power network, cooling & ventilation, Leistungsnetze, media supply, ...)
- **Minimum: assumes setup facility and/or (partial) automatisation**

B) 'Normal Operation': up to 25 people (machine setup, day-time)



- 4+2+1 'Skeleton Crew' + accelerator experts:
 - accelerator physicists, RF/BI/CO experts, beam-cooling experts, beam-line physicists, experimentalists, etc.
- Variable scenarios: + 15-20 People with >4h/day occupancy in FCC
 - setup of new (exotic) beam experiments: typ. 3-4 people
 - failure diagnostics and optimisation of the individual machine, accelerator sub-system, or beam production chain: typ. 3-4 people
 - Parallel machine development: typ. 5-8 people
 - **Hardware and Beam (Re-)Commissioning: 10-20 people (?!?)**
 - **Experiments tightly intertwined with accelerators (ESR, PANDA, etc.): typ. ~ 8 per experiment**
 - ...


3 fixed displays split between 2 workspaces CERN experience → FAIR:
independent fixed displays for each workspace

3 flat screens per workspace
1 keyboard 1 mouse



1 additional admin PC








Fixed-Displays (on wall)

Workstation
multiplexed on BPC

shared workstation
non-multiplexed




Information Density/Level of Detail

- I: semi-fixed displays – monitoring context, rare interactions (slightly overhead)
 - beam-transmission/beam-loss monitoring, primary experiment performance index, ...
- II: active user-interaction – automatically adapted to commissioning step (see FC²WG)
- III: non-multiplexed information:
 - Zugangskontrollsystem' (ZKS, access system), machine interlocks, ...

FAIR-Status

	HESR PANDA	241,2 Mev/u	p^-	4.23 ⁸ PPP	Status
Analysis with the new Experimenttarget					
	SUPER FRIS NUSTAR	1.1 Gev/u	^{238}U	8.55 ⁹ PPP	
Production / Investigation of exotic nuclei					
	HHT APPA	1 Gev/u	^{238}U	8.07 ¹¹ PPP	
High Energy Density Physics / Plasmaphysics					
	HTM BIOMAT	110 Mev/u	^{48}Ca	0.03 ⁶ PPP	
Radiobiological effects on human beings					
	X8 Nuclear Chemistry	4,75 Mev/u	^{48}Ca	8.96 ⁹ PPP	
Chemical Properties of Superheavy Elements at TASCA					
	M3 Materials Research	4,8 Mev/u	^{238}U	4.74 ⁹ PPP	
Radiation hardness of technologically relevant materials					
	CRYRING Atomic Physics	15 Mev/u	^{238}U	9.55 ⁹ PPP	
Commissioning Crying and Beam Diagnostic					
	Y7 NUSTAR / ENNA	5,25 Mev/u	^{50}Ti	0.09 ⁹ PPP	
SHE-Physik Element 199					
	S18-Dump Machine-Studies	1 Gev/u	^{238}U	3.39 ⁹ PPP	
Parallel Machine-Studies					





courtesy Achim Bloch-Spaeth


22.11.16 09:41 Beam stored for the CRYRING users

HESR PANDA 241.2 MeV/u p^- 4.23⁸ PPP Status ●
 Analysis with the new Experimenttarget
 Contact Person: Hans Mustermann Phone 4711
 Experiment-Cave: Phone 1508


14:33 2016-12-02
 Adjust Beam in CR
 14:00 2016-12-02
 Shiftchange in the Control Center
 12:30 2016-12-02
 Stable Beam in SIS 100




UNILAC
 stable Beam ●



SIS 18
 stable Beam ●





SIS 100
 stable Beam ●



CR
 Beam adjust ●




HESR
 Beamline open ●



courtesy Achim Bloch-Spaeth

Central meeting table:

- shift hand-over
- small ad-hoc meetings (→ + small meeting room)
- social functions



permanent usage
24h/7 during OP year
 (includes all accelerators, technical infrastructure needed for acc. operation)

reconfigurable usage

- storage ring experiments
- machine developments
- experiments tightly intertwined with acc.
- Hardware and Beam (Re-) Commissioning

12 Workspaces for short-notice stand-by personnel
 (|| R&D, acc. exp. Students, ..)
 (table with data / power connections)

Proposed BPC-Paradigm Scheme:

- 12 – Skeleton-crew (24h/7 OP)
 - 6 parallel BPCs/operators
 - 3 – Cryogenics (non-multiplexed)
 - 3 – Technical Infrastructure (non-m.)
- 5 – Island/Bay #1 – *reconfigurable usage*
 - storage ring/accelerator-kin experiments
 - machine developments
 - Hardware (HWC) & Beam (Re-)Commissioning (BC)
- 5 – Island/Bay #2 – *reconfigurable usage*
 - *as above*
- 2 – *generic short-term consoles (debugging & shift leaders)*


Classic scheme (deprecated):

- 5 – primary beam accelerators (UNILAC → SIS18 → SIS100)
- 3 – ESR, CRYRING, CR
- 2 – HESR
- 2 – SuperFRS
- 3 – Cryogenics
- 3 – Technical Infrastructure
- 5 – accelerator-kin experiments
- 2 – generic short-term debugging consoles (+ shift leaders)




Workstation distribution




Several options have been studied by the consultants (GTD, CCD), the CCC-WG and the IDOC. A one-day workshop gathered the IDOC and the CCC-WG, moderated by M.Clark (CCD), and chaired by S.Baird, AB/OP group leader, allowed to develop a model satisfactory for all parties.



CCD Layout A - 14/11/2003



CCD Layout B - 18/12/2003




Need similar user iteration at FAIR:
Accelerator operations, machine experts (& SPLs), GA/TI, experiments, ... tbd.


Appendix

- **mind. 600 m² Nutzfläche**
 - Mindestens 5 bis 25 Arbeitsplätze (Vorgaben ASR A1.2 – Abs. 5.4: 12 - 15 m²/Person, 60% effective Nutzfläche → siehe Appendix)
 - **klare Kommunikationslinien → offene unbehinderte Sicht (→ frei von Säulen)**
- **Deckenhöhe: > 3 m (optim. 5 m)**
- **Doppelboden: mind. 15 cm bzw. 50 cm falls Ent-/Belüftung benötigt**
 - N.B. getrennte Lüftung für Raum und Unterboden
- **Raumklima: (20-24) ± 1° C, 30-70 % Luftfeuchte, max. 0.1 m/s Luftgeschw.**
- **Beleuchtung: ≥ 500 lx (regelbar, DIN EN 12464-1, E DIN 5035-7)**
 - Gesetzlicher Tageslichtanteil & direkte indirekte Beleuchtung (ggf. Vollspektrumlicht)
- **Akustik** (Einfluss auf: Bodenbeläge, Wandverkleidungen, Abtrennwände, etc.)
 - **Lärmpegel: <35 dB(A) (Hintergrund) bzw. <35-45 dB(A)** (10+ Personen, BildscharbV & BAuA)
 - Nachhall-Zeit: 0.4 (best) bzw. max. 0.6 s (DIN EN ISO 9241 – part 6)
 - **N.B. Schließt Klimaanlage, PCs, Drucker, usw. ein!**
 - **Geringerer Rauschhintergrund → geringere Gesprächslautstärken → geringere Störfaktoren für andere HKR Nutzer → bessere Konzentration → ...**
- **N.B. Elektrische Leistung: ~40 kW**

Kein Einzelobjekt sondern:

- **Eigentliche Hauptkontrollraum: ~ 600 m²**
- **Zusätzliche Flächen**
 - Gesetz. 'Pausenraum' bzw. Küche (ArbStättV §6): > 25 m² (optimal: ~ 60 m²)
 - Aufstellflächen für IT/CO Infrastruktur: ~ 200-300 m² ??
 - **Kleiner Besprechungsraum (~ 10-15 Personen): ~ 60 m²**
 - Unmittelbar an HKR angrenzend
 - **Großer Konferenzraum (~ 25 + 25 Personen): ~ 60-100 m²**
 - bisher nicht existent bzw. mangelhaft: „Beschleunigerbesprechungszimmer“
 - Kurze Laufdistanz (< 100 m) zum HKR
 - **Besuchergalerie für 25 Besucher + Ausstellung (100-200 Besucher/Tag)**
 - Abgetrennter Arbeitsplatz für Betriebsleitung: ~ 15 m²
 - Versorgungsflächen & Technische Gebäudeausrüstung: ~ ??? m²
 - Druckerraum (~ 5 m², tbc.)
 - Gesetzlich (BAuA) nicht zwingend für >25 m³ + keine Dauernutzung von Druckern im HKR! (N.B. Meisten Laserdrucker/Kopierer erfüllen Feinstaubpartikel Norm)
- **Rezeption?**






constant
~ 75 ± 5 %

Based on: U. Scheeler, S. Reimann, P. Schütt et al., "Accelerator Operation Report", GSI Annual Scientific Reports 1992 – 2015 + 2016 (D. Severin)
https://www.gsi.de/en/work/research/library_documentation/gsi_scientific_reports.htm
 N.B. ion source exchanges are factored out from UNILAC & SIS18 data (~ constant overhead)
 Availability: experiments + detector tests + machine development + beam to down-stream accelerators;
 Down-time: unscheduled down-time + standby; Operation: accelerator setup + re-tuning

* 2018 operation limitations:
 • only ½ UNILAC (w/o A3 & A4)
 • only 1 element in SIS18

- Beam-on-Target figure of merit (FoM) of ~75% → FAIR-BoT (efficiency ϵ_{FAIR}):

$$\epsilon_{\text{FAIR}} := \prod_i^{n_{\text{machines}}} \epsilon_i = \epsilon_{\text{UNILAC}} \cdot \epsilon_{\text{SIS18}} \cdot \epsilon_{\text{SIS100}} \cdot \epsilon_{\text{SuperFRS}} \cdot \epsilon_{\text{CR}} \cdot \epsilon_{\text{HESR}} \cdot \dots$$



+ new operational challenges:

operating beyond present beam parameter envelope, x10-100 higher intensities, x10 higher energies → machine protection & losses/activation become an issue

“... have to improve!”